

BLUE Landscape & Outdoor Solutions

4175 Broken Back Road
Naples, FL 34119
(239) 566-2583
info@experienceblue.net
www.experienceblue.net

ESTIMATE



ESTIMATE NUMBER

19854

ESTIMATE DATE

04/09/2024

KW Property Management & Consulting
11611 Paseo Grande Blvd
Fort Myers, FL 33912

PROJECT DESCRIPTION	QTY	RATE	AMOUNT
---------------------	-----	------	--------

Paseo HOA,
Fort Myers, FL

1 74,150.00 74,150.00

Four Bocce Ball courts

Remove existing court surrounds to include all wood and dispose of off site. The ball racks will be saved for re use.

Existing irrigation will be capped off by on site irrigation company.
Excavate down and remove approximately 10 inches and remove spoils off site.
Excavate down the center of each court and install one 4" perforated pipe and extend to the storm drain to the north of the site. Pipe will be covered with 57 stone and blinded off with 89 stone.
Install fabric over the top of rock.

Supply and install two courses of Tremron Stonegate wall block.
Block will two courses high with a decorative matching cap.
Install 1" by 6" IPE on inside edge and will have matching IPE plugs to hide Fasteners.

Install lime rock to bring inside of court to 7" below top of wall and compact.
Supply and install Global Synthetic turf Bi Putt 60 artificial turf over 1" of bedding sand

Install concrete border along inside edge of wall and turf will be bonded to it.

In fill the turf with 60 mesh sand at 2LB per sq ft and power broom into sward.

Reinstall pavers that were disturbed during construction.

Reinstall ball rack

PLEASE NOTE:

All jobs require 50% deposit at time of contract acceptance. PAYMENT TERMS: Payment for services is due as noted above. After thirty (30) days past due, interest will accrue at 1.5% per month.

BLUE will be entitled to all court costs, attorneys fees and costs, etc., if collection becomes necessary.

Proposal excludes the following:

- Permitting
- Demo and excavation of any kind unless specified
- Any concrete work unless specified above
- Due to material costs price only valid for 30 days
- Due to manufactures not giving lead times please allow 8-16 weeks for paver materials
- Modifications or repairs to existing irrigation or utilities.
- All removal or installation of plant material to include turf.
- When material is ready for delivery, room must be created on site to store material until project is ready.
- A 50% deposit will be required prior to ordering materials.
- No protection included for any existing surfaces to be kept in tact.

See link to standard terms and conditions.
www.marianilandscape.com/LLC/CoC.pdf

Thank you for your business.

ESTIMATE TOTAL: \$74,150.00

Mariani Enterprises, LLC dba BLUE Landscape & Outdoor Solutions

Accepted By: _____

Travis Otto
Travis Otto (Apr 23, 2024 14:53 EDT)

Accepted Date: _____

All jobs require 50% deposit at time of contract acceptance. PAYMENT TERMS: Payment for services is due as noted above. After thirty (30) days past due, interest will accrue at 1.5% per month.

BLUE will be entitled to all court costs, attorneys fees and costs, etc., if collection becomes necessary.